

**As per your enquiries please find the Bill of Quantities for Supply, installation, testing and commissioning installation works at The Little Theatre Club Mombasa.
Tender No: Bok/LTC/10/2017**

REFURBISHMENT OF LITTLE THEATRE CLUB- MOMBASA

BILL NO. 1 PRELIMINARIES

ITEM	DESCRIPTION	QTY	UNIT	RATE	AMOUNT
1	Discrepancies clause 1.02				
2	Conditions of sub-contract Agreement clause 1.03				
3	Payments clause 1.04				
4	Site location clause 1.06				
5	Scope of contract works clause 1.08				
6	Extent of contractors duties clause 1.09				
7	Firm price contract clause 1.12				
8	Variation clause 1.13				
9	Prime cost and provisional sum clause 3.14 (insert profit and attendance which is a percentage of expended PC or provisional sum				
10	Bond clause 1.15				
11	Government legislation and regulations clause 1.16				
12	Import duty and VAT clause 1.17 (Note this clause applies for materials supplied only VAT will also be paid by the subcontractors as allowed in eh summary page)				
13	Insurance company fees clause 1.18				
14	Provision of services by the Main contractor clause 1.19				
15	Samples and materials generally clause 1.21				
16	Supplies clause 1.20				
17	Bills of quantities clause 1.23				
18	Contractors office in Kenya clause 1.24				
19	Builders work clause 1.25				
	Sub Total carried to page H/2				
	H/1				

REFURBISHMENT OF LITTLE THEATRE CLUB- MOMBASA

BILL NO. 1 PRELIMINARIES

ITEM	DESCRIPTION	QTY	UNIT	RATE	AMOUNT
				B/F	
20	Setting to work and regulating system clause 1.29				
21	Identification of plant components clause 1.30				
22	Working drawings clause 1.32				
23	Records Drawings (As Installed) and instructions clause 1.33				
24	Maintenance Manual clause 1.34				
25	Hand over clause 1.35				
26	Painting clause 1.36				
27	Testing and inspection - manufactured plant clause 1.38				
28	Testing and inspection - installation clause 1.39				
29	Storage of materials clause 1.41				
30	Initial Maintenance Clause 1.42				
31	Attendance Upon Tradesmen etc (Insert percentage only) clause 1.58				
32	Local and other authorities notice clause 1.60				
33	Temporary Works clause 1.63				
34	Patent Rights clause 1.64				
35	Mobilization and Demobilization clause 1.65				
37	1.70)				
38	Supervision by Engineer and site meetings clause 1.67				
39	Allow for profit and attendance for the above				
40	Amendment to Scope of subcontract works clause 1.68				
41	Contract obligation and employers obligation clause 1.69				
42	Any other preliminaries				
	TOTAL TAKEN TO ELECTRICAL SUMMARY				
PAGE H/2					

BILL NO.2 SCHEDULE 1

ITEM	DESCRIPTION	QTY	UNIT	RATE	AMOUNT KSH
	SUPPLY, INSTALL, TEST & COMMISSION				
A	RESTAURANT				
1.00	Lighting points wired in 3 x 1.5mm ² PVC SC cable drawn in existing conduit wired as:-				
	(i) 1 way switching	8	NO		
	(ii) 2 way switching	6	NO		
2.00	White moulded plate switches as Crabtree as:-				
	(i) 1 gang 1 way	1	NO		
	(ii) 2 gang 1 way	3	NO		
3.00	Lighting fittings complete with energy saving bulbs and tubes:-				
	(i) Pendant fitting with wide circular transparent decorative shade as Massive 88180NW/1	6	NO		
	(ii) Adjustable goose neck picture light wall bracket as Micromark or approved equivalent	8	NO		
4.00	3 x 2.5mm ² PVC SC Cables drawn in existing conduits to ring main socket outlets	6	NO		
5.00	13A White Moulded plate Socket Outlets as Crabtree:-				
	(i) Twin	9	NO		
6.00	3 x 2.5mm ² PVC SC cables drawn in existing concealed conduits to ceiling mounted sweep fans	6			
7.00	TV Aerial outlet points interlinked via 25MM dia HG PVC conduits including outlet plates and draw wire.	1	NO		
B	BAR				
1.00	Lighting points wired in 3 x 1.5mm ² PVC SC cable drawn in existing conduit wired as:-				
	(i) 1 way switching	4	NO		
	(ii) 2 way switching	6	NO		
2.00	White moulded plate switches as Crabtree as:-				
	(i) 1 gang 1 way	1	NO		
	(ii) 2 gang 1 way	3	NO		
3.00	Lighting fittings complete with energy saving bulbs and tubes:-				
	(i) Pendant fitting with traditional basket decorative shade as existing	6	NO		
	(ii) Adjustable goose neck picture light as Micromark or approved equivalent	4	NO		
TOTAL TAKEN TO NEXT PAGE					

REFURBISHMENT OF LITTLE THEATRE CLUB- MOMBASA

BILL NO.2 REFURBISHMENT OF LITTLE THEATRE CLUB - MOMBASASCHEDULE 1

ITEM	DESCRIPTION	QTY	UNIT	RATE	AMOUNT KSH
	SUPPLY, INSTALL, TEST & COMMISSION				
	(ii) Wall mounted lantern with golden brown finish as Micromark or approved equivalent	8	NO	B/F	
	(iv) Eyeball fixed downlight as micromark or approved equivalent	6	NO		
4.00	3 x 2.5mm ² PVC SC Cables drawn in concealed 20mm dia. PVC conduits to ring main socket outlets points	6	NO		
5.00	3 x 2.5mm ² PVC SC Cables drawn in existing conduits to ceiling mounted sweep fans	6	NO		
6.00	13A White Moulded plate Socket Outlets as Crabtree:- (ii) Twin	6	NO		
7.00	WIFI/data outlet points interlinked via 20mm dia. HG PVC conduit including RJ outlet plates and drawn wire	6	NO		
8.00	TV Aerial outlet points interlinked via 25MM dia HG PVC conduits including outlet plates	2	NO		
c	ENTRANCE FOYER				
1.00	Lighting points wired in 3 x 1.5mm ² PVC SC cable drawn in existing conduit wired as:- (i) 2 way switching	20	NO		
2.00	White moulded plate switches as Crabtree as:- (i) 1 gang 1 way (i) 2 gang 2 way (ii) intermediate	1 2 4	NO NO NO		
3.00	Lighting fittings complete with energy saving bulbs and tubes:- (i) Wall mounted uplights with wrought iron finish as Micromark (ii) Ground mounted totally enclosed waterproof spotlight	14 6	NO NO		
4.00	3 x 2.5mm ² PVC SC Cables drawn in existing conduits to ring main socket outlets	2	NO		
5.00	13A White Moulded plate Socket Outlets as Crabtree:- (i) twin	2	NO		
TOTAL TAKEN TO NEXT PAGE					

REFURBISHMENT OF LITTLE THEATRE CLUB- MOMBASA

BILL NO.2 SCHEDULE 1

ITEM	DESCRIPTION	QTY	UNIT	RATE	AMOUNT KSH
	SUPPLY, INSTALL, TEST & COMMISSION			B/F	
D	DANCE HALL				
1.00	Lighting points wired in 3 x 1.5mm ² PVC SC cable drawn in existing conduit wired as:- (i) 1 way switching	8	NO		
2.00	White moulded plate switches as Crabtree as:- (i) 1 gang 1 way	2	NO		
3.00	Lighting fittings complete with energy saving bulbs and tubes:- (i) Pendant fitting with decorative shade	8	NO		
4.00	3 x 2.5mm ² PVC SC Cables drawn in concealed 20mm dia. PVC conduits to ring main socket outlets points	4	NO		
5.00	13A White Moulded plate Socket Outlets as Crabtree:- (i) Single (ii) Twin	2 2	NO NO		
6.00	3 x 2.5mm ² PVC SC cables drawn in existing conduits to fan switch points	6	NO		
7.00	TV Aerial outlet points interlinked via 25MM dia HG PVC conduits including outlet plates and draw wire.	3	NO		
	STUDIO				
8.00	Lighting points wired in 3 x 1.5mm ² PVC SC cable drawn in existing conduit wired as:- (i) 1 way switching	6	NO		
\$9.00	White moulded plate switches as Crabtree as:- (i) 1 gang 1 way	3	NO		
\$10.00	Lighting fittings complete with energy saving bulbs and tubes:- (i) 18W Downlight GreenLEDi 1200 as Philips	8	NO		
\$11.00	3 x 2.5mm ² PVC SC Cables drawn in existing conduits to ring main socket outlets	6	NO		
\$12.00	13A White Moulded plate Socket Outlets as Crabtree:- (ii) Twin	6	NO		
\$13.00	3 x 2.5mm ² PVC SC Cables drawn in existing conduits to Air conditioning unit 20A DP Switch	3 3	NO NO		
	TOTAL TAKEN TO NEXT PAGE				

REFURBISHMENT OF LITTLE THEATRE CLUB- MOMBASA

BILL NO.2

SCHEDULE 1 - ELECTRICAL INSTALLATIONS

ITEM	DESCRIPTION	QTY	UNIT	RATE	AMOUNT KSH
	SUPPLY, INSTALL, TEST & COMMISSION				
E	GYMNASIUM			B/F	
1.00	Lighting points wired in 3 x 1.5mm ² PVC SC cable drawn in existing conduit wired as:- (i) 1 way switching	22	NO		
2.00	White moulded plate switches as Crabtree as:- (i) 1 gang 1 way	3	NO		
3.00	Lighting fittings complete with energy saving bulbs and tubes:- (i) 1 x 600mm 18W single batten fluorescent fitting as Thorn (ii) 2 x 36W 1200mm twin batten fluorescent fitting as Thorn (iii) Pendant complete with ceiling rose and lampholder (iv) Fluorescent bulkhead fitting as Thorn OBV (v) Spherical Screwneck lighting fitting as Thorn	3 8 6 6 1	NO NO NO NO NO		
4.00	3 x 2.5mm ² PVC SC Cables drawn in existing conduits to ring main socket outlets	14	NO		
5.00	13A White Moulded plate Socket Outlets as Crabtree:- (ii) Twin	14	NO		
6.00	3 x 2.5mm ² PVC SC Cables drawn in existing conduits to ceiling mounted sweep fans	6	NO		
7.00	2 - compartment powder coated and primed with anti rust paint 50 x 150mm trunking	70	LM		
8.00	6 Ways Consumer Unit as Schneider or approved equivalent	3	NO		
9.00	The following miniature circuit breakers:- (i) 5A SP (ii) 10A SP (iii) 20A SP (iv) 30A SP	3 2 3 6	NO NO NO NO		
10.00	2C 6sq.mm PVC SWA PVC armoured copper cables	60	M		
TOTAL TAKEN TO NEXT PAGE					

REFURBISHMENT OF LITTLE THEATRE CLUB- MOMBASA

BILL NO.2

SCHEDULE 1

ITEM	DESCRIPTION	QTY	UNIT	RATE	AMOUNT KSH
	SUPPLY, INSTALL, TEST & COMMISSION				
11.00	Lighting points wired in 3 x 1.5mm ² PVC SC cable drawn in existing Concealed 20mm dia. Hg conduit wired as:- (i) 1 way switching	11	NO		
12.00	White moulded plate switches as Crabtree as:- (i) 1 gang 1 way	3	NO		
13.00	Lighting fittings complete with energy saving bulbs and tubes:- (i) 1200MM 2 x 36W twin batten fluorescent as Thorn or approved equivalent (ii) 1200MM 2 x 36W twin fluorescent with non scratch washable diffuser as Thorn or approved equivalent (iii) Mains voltage insectocutor as Thorn or approved equivalent	2 8 1	NO NO NO		
14.00	3 x 2.5mm ² PVC SC Cables drawn in existing concealed 20mm dia. PVC conduits to ring main socket outlets points	6	NO		
15.00	13A White Moulded plate Socket Outlets as Crabtree:- (i) Twin	6	NO		
16.00	32mm diameter galvanised steel heavy gauge steel conduit	60	LM		
17.00	4 x 6.0mm ² PVC SC cables drawn in concealed 25mm dia. Steel conduits to cooking Island	3	NO		
18.00	32A TPN Metal clad Isolator	3	NO		
19.00	2 x 2.5mm ² PVC SC cables drawn in 25mm dia. Steel conduits to undersink water heater	4	NO		
20.00	20A DP water heater switch with NEON indicator as Crabtree	4	NO		
21.00	9 Ways Distribution board as Schneider or approved equivalent	1	NO		
22.00	The following Miniature Circuit Breakers as Schneider or approved equal:- i) 32A SP ii) 30A SP iii) 20A SP iv) 10A SP v) Spares	3 6 4 10 4	NO NO NO NO NO		
TOTAL TAKEN TO NEXT PAGE					

REFURBISHMENT OF LITTLE THEATRE CLUB- MOMBASA

BILL NO.2

SCHEDULE 1

ITEM	DESCRIPTION	QTY	UNIT	RATE	AMOUNT
	SUPPLY, INSTALL, TEST & COMMISSION				
F	VERANDAH, PARKING AND SECURITY LIGHTING			B/F	
1.00	Lighting points wired in 3 x 1.5mm ² PVC SC cable drawn in existing Concealed 20mm dia. Hg conduit wired as:- (i) 1 way switching	16	NO		
2.00	White moulded plate switches as Crabtree as:- (i) 1 gang 1 way	3	NO		
3.00	Lighting fittings (i) Side entry wall mounted street light fitting complete with angle arm mounting bracket as Philips LED smartbright (ii) Wall mounted LED Bulkhead fitting as Philips EnduraLED Bulkhead (ii) Top entry Garden lighting Luminaire as Philips LED Post - Top	4 12 8	NO NO NO		
4.00	2C 2sq.mm PVC SWA PVC armoured cable	120	LM		
5.00	Trenching, laying and tiling to a depth of 600x300x600	120	LM		
6.00	5M Post top lighting column primed with antirust paint and aluminium paint finish	8	NO		
7.00	Earthing of 2No. of the above	2	item		
8.00	A photocell to fit 70-75lux switch on level and 1.5 maximum differential as THORN QPK	1	NO		
9.00	10A 240V 2 pole contactor as Telamecanique or approved equivalent	1	NO		
TOTAL TAKEN TO ELECTRICAL SUMMARY PAGE					

REFURBISHMENT OF LITTLE THEATRE CLUB- MOMBASA

REFURBISHMENT OF LITTLE THEATRE CLUB - MOMBASA

BILL NO.2 SCHEDULE 2 - THEATRE LIGHTING

ITEM	DESCRIPTION	QTY	UNIT	RATE	AMOUNT KSH
	SUPPLY, INSTALL, TEST & COMMISSION				
A	AUDITORIUM				
	GENERAL				
1.00	Lighting points wired in 3 x 1.5mm ² PVC SC cable drawn in existing Concealed 20mm dia. Hg conduit wired as:- (i) 1 way switching (ii) 2 way switching	18 31	NO		
2.00	White moulded plate switches as Crabtree as:- (i) 1 gang 1 way (i) 1 gang 2 way (iii) Two way dimmer switch	4 6 2	NO NO NO		
3.00	Lighting fittings (i) 1200mm 36W light fitting as Philips Greenperform batten (i) 600mm 18W light fitting as Philips Greenperform batten Surface mounted luminaire with 28W dimmable LED (iii) lamps as Thorn Chalice 190 or approved equivalent 22W Downlights with dimming solution as Philips GreenPerform (iv) LED Exit door light signs as Thorn or approved equivalent	15 8 16 20 10	NO NO NO NO NO		
4.00	Power Points (i) 3 x 2.5mm ² PVC SC Cables drawn in existing concealed 20mm dia. PVC conduits to ring main socket outlets points (ii) 13A Twinn White Moulded plate Socket Outlets as Crabtree:- (iii) 3 x 2.5mm ² PVC SC Cables drawn in existing concealed 20mm dia. PVC conduits to Sweep fans in the control room (iv) 4C x 6.00sq mm armoured PVc SWA PVC cable to AC control unit	12 12 3 60	NO NO NO M		
TOTAL TAKEN TO COLLECTION PAGE					

REFURBISHMENT OF LITTLE THEATRE CLUB- MOMBASA

BILL NO.2 REFURBISHMENT OF LITTLE THEATRE CLUB - MOMBASA

ITEM	DESCRIPTION	QTY	UNIT	RATE	AMOUNT KSH
	SUPPLY, INSTALL, TEST & COMMISSION				
1.00	STAGE LIGHTING				
	(i) Lighting points wired in 3 x 1.5mm ² PVC SC cable drawn in Concealed 20mm dia. Hg conduit to be controlled from the lighting control console	40	No		
2.00	Lighting fittings				
	The following LED light fittings complete with all accessories:-				
	(i) LED Smooth washer Diffuser as ETC source 4 or approved equivalent	4	No		
	(ii) MH 1 LED Profile fixture moving head with required Lenses as ETC Colorsource or approved equivalent	4	No		
	(iii) LED PAR, XLR fixtures complete with lenses as ETC ColorSource or approved equivalent	15	No		
	(iv) Colorsource Sptlight Engine w, Barrel, XLR as ETC or approved wquivalent	6	No		
	(v) S 4 36° Lens tube black as ETC or approved equivalent	2	No		
	(vi) S 4 26° Lens tube black as ETC or approved equivalent	2	No		
3.00	Lighting Control				
	(i) 40 AV lighting control Console as ETC ColorSource or approved equivalent	1	No		
	(ii) 24 x 10A ThruPower Racks as ETC ColorSource or approved equivalent	2	No		
	(iii) ENTTEC 1 in 8 out Splitter Buffer as ETC or approved Equivalent	1	No		
	(iv) Wall Sleeve for ENTTEC 1 in 8 out Splitter Buffer as ETC or approved Equivalent	1	No		
4.00	Fixtures				
	(I) Pre-wired Bar with 4 plug-in sockets and DMX - stage	3	No		
	(II) Pre-wired Bar with 4 plug-in sockets and DMX - Apron	1	No		
	(iii) Pre-wired Bar with 2 plug-in sockets and DMX - side	2	No		
5.00	Allow for Cabling ,software and networking	1	item		
6.00	Allow for Training of 2No. Operators	1	item		
TOTAL TAKEN TO COLLECTION PAGE					

BILL NO.2 SCHEDULE 3 - SOUND SYSTEM

ITEM	DESCRIPTION	QTY	UNIT	RATE	AMOUNT KSH
A	SUPPLY, INSTALL, TEST & COMMISSION				
	SOUND SYSTEM				
	The following Sound System as Midas or approved equivalent				
1.00	Main System				
	(i) EV XLM Electro voice 12 inch 2 way speaker	2	No		
	(ii) EV XLM Electro voice 15 inch 2 way subwoofer	2	No		
	(iii) EV XLM Electro voice dual channel Amplifier	2	No		
	(iv) EV XLM Electro voice ZXL wall Mount bracket	2	No		
2.00	Cabling and Rack				
	(i) 2 core 1.5sq.mm sound cable as prosound or approved equivalent	200	LM		
	(ii) 10U Rack as Prosound or approved equivalent	2	No		
	(iii) Amphenol Speaker connectors as Prosound or approved equivalent	12	No		
3.00	Stage Monitors				
	(i) EV ZLX 12 inch powered loudspeaker as Midas or approved equivalent	4	No		
	(ii) 10M Microphone XLR cable as Prosound or approved equivalent	4	No		
4.00	Mixing Console				
	(i) Hybrid Analog/Digital Mixing Console as Midas DM16 or approved equivalent	1	No		
5.00	Microphone and DI's System as Midas or approved equivalent				
	(i) Audio Technica 3000 series Handheld wirelees	4	No		
	(ii) Audio Technica Hyper Cardioid Dyna. Vocal Mic	2	No		
	(iii) Audio Hyper Cardioid instrument Mic	4	No		
	(iv) Audio Technica clip on instrument Mic	2	No		
	(v) Audio Technica side address condenser inst. Mic	2	No		
	(vi) Audio Technica Kick Drum Mic	1	No		
	(vii) Audio Technica wireless Beltpack system	2	No		
	(viii) DPA Headset Mic	2	No		
	(ix) DPA Adapter Belt Packs	2	No		
	(x) Proco Heavy duty DI Box	2	No		
	(xi) Jamstand Tripod Mic Stand	20	No		
	(xii) Jamstand Kick Drum/Amp stand Mic Stand	2	No		
6.00	System processor, Playback and effects unit				
	(i) Electro voice sound digital 2 input sound system processor	1	No		
	(ii) Live Application TC XL dual effects unit	1	No		
	(iii) Deno IU CD/Media Player				
	(iv) Interconnecting and turn around cables	1	item		
7.00	Microphone and DI's Cabling				
	(ii) Both to stage and Pit cabling in 16 pair cables	1	item		
	(iii) 20M microphone cables	10	No		
	(iv) 10M Microphone cable	10	No		
	TOTAL TAKEN TO NEXT PAGE				

REFURBISHMENT OF LITTLE THEATRE CLUB- MOMBASA

BILL NO.2 REFURBISHMENT OF LITTLE THEATRE CLUB - MOMBASA

ITEM	DESCRIPTION	QTY	UNIT	RATE	AMOUNT KSH
	SUPPLY, INSTALL, TEST & COMMISSION				
	(i) 5M microphone cables	10	No	B/F	
	(ii) Jack to jack cables	10	No		
8.00	Communication				
	(i) Commpac headset/mic single muff	4	No		
	(ii) compmac Beltpack single channel	2	No		
	(iii) Power supply to user stations	4	No		
	(iv) Listener station	1	No		
	(v) Dressing room station	1	No		
9.00	Allow for Training of 2No. Operators	1	item		
10.00	Allow for any other item to make the installation complete	1	item		
TOTAL TAKEN TO SUMMARY PAGE					

REFURBISHMENT OF LITTLE THEATRE CLUB- MOMBASA

BILL NO. 2 SCHEDULE 4 - POWER DISTRIBUTION AND METERING

ITEM	DESCRIPTION	QTY	UNIT	RATE	AMOUNT
	SUPPLY, INSTALL, TEST & COMMISSION				
A	POWER DISTRIBUTION AND METERING				
1	(i) 4 Way 100A TPN wall mounted powder coated Meterboard fabricated from heavy duty steel to accommodate 1No. 3 phase Meter as Power Technics	5	NO		
2	The following as Schnieder :-				
	(i) 63A TP Pole MCCB	1	NO		
	(ii) 80A TP MCCB	1	NO		
	(iii) 60A SP MCCB				
	(iv) Earth the above Meterboards as per the IEE regulation and to KP&LC approval	1	Item		
	(v) 8 Ways Distribution Board as Schneider or approved equivalent	1	NO		
	(vi) 6 Ways Distribution Board as Schneider or approved equivalent	1	NO		
	(vii) 6 ways MCB consumer unit as Schneider	1	NO		
3	The following as Crabtree:-				
	(i) 10A SP MCB	12	NO		
	(ii) 20A SP MCB	6	NO		
	(iii) 30A SP MCB	8	NO		
	(iv) 32A SP MCB	4	NO		
	(v) BLANKED SPAREWAYS	18	NO		
4	Cables				
	(i) 4 x 16mm ² sc copper cables in 50mm dia. heavy gauge pvc conduit from Cable loop - in box to DB in the Kitchen	30	LM		
	(ii) 4 x 16mm ² sc copper cables in 50mm dia. heavy gauge pvc conduit from Cable loop - in box to DB in the Theatre Auditorium	30	LM		
	(iii) 3 x 6mm ² sc copper cables in 32mm dia. heavy gauge pvc conduit from Cable loop - in box to DB in the Dance Hall	50	LM		
	(ii) 4C 70mm ² PVC SWAPVC armoured cable from Generator to Meterboard	60	LM		
TOTAL TAKEN TO SUMMARY PAGE					

REFURBISHMENT OF LITTLE THEATRE CLUB- MOMBASA

BILL NO. 2 SCHEDULE 5 - PROVISIONAL SUMS

ITEM	DESCRIPTION	AMOUNT
A	Allow for provisional sum of Kenya shillings Fifty thousands only for preparation and production of 5No. sets of "As installed Drawings" hard copies negatives and soft copies in AutoCAD 2000 on CD/DVD	50,000.00
B	Allow for profit, taxes on the above item	
C	Allow sum of Kenya shillings Three Hundred Thousand for price fluctuations as per clause 28.3 & 28.4 of the sub contract document.	300,000.00
D	Allow sum for training levy to be paid directly to the State Department of Public Works Project Manager's account	150,000.00
E	Allow for profit, taxes and attendance on the above item	
F	Allow for airtime for ten (6No.) Project officers at a rate of Kshs 3,000.00 per officer per month for the entire project duration.	108,000.00
J	Allow for profit, taxes and attendance on the above item	
K	Allow a Contingency sum to be expended at the discretion of the Project Manager.	300,000.00
TOTAL TAKEN TO SUMMARY PAGE		

SUMMARY PAGE

ITEM	DESCRIPTION	AMOUNT KSHS
1.00	BILL NO. 1 - PRELIMINARIES	
2.00	BILL NO. 2 - SCHEDULE 1 - GENERAL ELECTRICAL INSTALLATIONS	
3.00	BILL NO. 2 - SCHEDULE 2 - THEATRE LIGHTING	
4.00	BILL NO. 2 - SCHEDULE 3 - THEATRE SOUND SYSTEM	
5.00	BILL NO. 2 - SCHEDULE 4 - POWER DISTRIBUTION AND METERING	
6.00	BILL NO. 2 - SCHEDULE 5 - PROVISIONAL SUMS	
TOTAL TAKEN TO FORM OF TENDER		

Amount of tender in words: KenyaShillings.....

.....

Tenderers Signature and Stamp.....

Address.....

Date.....

Witness: Name and Signature.....

Address.....

Date

Address.....

Date

